

BOOST LOP – Train 1

Column Flushing MAM-101 FWKO ILIC-101

PURPOSE: Level Switch Test

OBJECTIVE: Safely Shutdown Process Testing

SCOPE: Safely flush level column for ILIC 101

1 CLASSIFICATION DATA:

Approved: *August 1, 2017*

Review Cycle: [2] year

Reviewers: Local SMEs

Approver: Operations Supervision

Curt Bourgeois

Carmen Berry

Craft:

Process Engineer

Man-hours:

20 min

SAFETY, ENVIRONMENTAL, AND ASSET CONSEQUENCES

<u>RAM Rating</u>	<u>Severity & Likelihood</u>	<u>Rating</u>
Safety Consequence	Slight Injury, Heard of in industry	P1B
Environmental Consequence	No Impact, Never heard of in industry	E0A
Asset Consequence	Slight damage less than \$10,000, Heard of in industry	A1B

Permits and plans (those checked are required)			
X	JSA		Hot Work Permit
	Safe Work Permit		Fall Rescue Plan
	Safe Work Plan		Confined Space Entry
	Lock Out/Tag Out		Leadership Walkthrough
	Isolated work is allowed	X	Trip Tricky Tasks
	Step Sign off Required (High Rating)	X	Statement of Fitness (may be required)
Special PPE Required (those checked are required)			
	Chemical Resistant Gloves		Additional Hearing Protection-Ear Muffs
	Face Shield		Respirator
	Chemical Resistant Goggles		Fresh Air Pack
	Chemical Resistant Apron		

TOOLS/EQUIPMENT REQUIRED

- Radios
- Hand tools
- Proper PPE

2 CONSUMABLES (MMR IF APPLICABLE)

MMR #	Consumables Description	Qty
	N/A	

3 PARTS (MMR IF APPLICABLE)

MMR #	Parts Description	Qty
	N/A	

SPECIAL EXECUTION CONSIDERATION

1. All procedures require sign off upon completion each step.

WORK INSTRUCTION

Signoff	Operation Step
1. _____	Have CRO place ILIC - 101 in Manual Control.
2. _____	Have CRO communicate when controller is in Manual.
3. _____	Close manual column valve M101 - 9. Lower isolation valve on level column.
4. _____	Close manual column valve M101 - 11. Upper isolation valve on level column.
5. _____	Remove plug.
6. _____	Open drain valve on bottom of float cage.
7. _____	Drain fluids into a bucket with secondary containment. Trapped pressure may be present. Uncontrolled pressure release could result in bodily injury or death. Wear gloves and safety glasses.
8. _____	Remove plug and open vent on top of float cage and vent to a location away from any personnel. Slowly open vent--releasing pressure a little at a time. <i>Note: This will verify that all fluids have been drained.</i>
9. _____	Close the vent valve and re-install plug.
10. _____	Close the drain valve and re-install plug.
11. _____	Open manual column valves M101 - 11. Upper isolation valve on level column
12. _____	Open manual column valves M101 - 9. Lower isolation valve on level column

13. _____ Observe that the fluid rise and that the ILIC returns to a normal operating condition.

14. _____ Dispose of fluids collected from performing the task by dumping in Wet Oil Tank.
